

UNITED STATES GOVERNMENT

Memorandum

ENGINEERING
FILE COPY

TO : P. M. Price, State Conservation Engineer,
SCS, Temple, Texas

DATE: January 25, 1962

FROM : Howard Matson, Head, E&WP Unit,
SCS, Fort Worth, Texas

SUBJECT: OPERATIONS - Materials Testing Section Report,
Texas, WP-08, Guadalupe River,
Plum Creek, Site 12

ATTACHMENTS

- | | |
|---|----------|
| 1. Form SCS-35, Plan and Profiles for Geologic Investigations | 3 sheets |
| 2. Form SCS-352, Compaction Curves | 4 sheets |
| 3. Form SCS-354, Soil Mechanics Laboratory Data | 3 sheets |
| 4. Form SCS-372, Recommended Use of Excavated Materials | 1 sheet |

INTERPRETATION OF DATA & RECOMMENDATIONS

Foundation

The underlying foundation material consists of shale at depths of 10' to 24'. The shale is overlain by CH and GC soils with low salt contents and low to moderate dispersion.

Based on the 20% size the foundation materials should have very low to moderate permeabilities.

At station 21 + 30 settlement due to consolidation of the foundation should not exceed 0.9' of which 20% may occur during a construction period of four months.

Centerline Cutoff

The depths of excavation shown in the following tabulation should provide an effective cutoff in slowly permeable materials.

RECOMMENDED CUTOFF DEPTHS

| <u>Station</u> | <u>Depth</u> | <u>Elevation</u> | <u>Bottom Materials</u> |
|----------------|--------------|------------------|-------------------------|
| 11 + 00 | 6.0 | 607.2 | Silty Clay |
| 17 + 00 | 7.0 | 600.2 | Silty Clay |
| 19 + 00 | 6.0 | 596.8 | Silty Clay |
| 21 + 30 | 10.0 | 587.4 | Shale |
| 22 + 00 | 9.0 | 587.5 | Silty Clay |
| 26 + 00 | 8.0 | 589.7 | Silty Clay |
| 30 + 00 | 8.0 | 595.9 | Silty Clay |
| 32 + 00 | 5.0 | 606.7 | Silty Clay |

Principal Spillway (Station 21 + 30 @ Dam)

Excavation for the foundation under the outlet structure should extend to a depth of approximately 10' at the intersection with the centerline of the dam.

At this depth settlement under the conduit foundation should be negligible. Settlement in 10' of materials surrounding the conduit foundation is estimated to be 0.9'.

Borrow and Excavation

AASHTO compaction tests were performed on two composite samples from the emergency spillway and two from the borrow area. Densities obtained are recorded on Form SCS-354. The samples tested classify as CH and GC soils. The CH materials represented by Curves 1 and 3 should be used in the interior of the embankment. The GC materials represented by Curves 2, 4 and composite number 7 should be used in the outer sections. A compaction test was not performed on composite sample number 7 from the new emergency spillway since this sample contained 83% gravel. It is suggested that this material be compared with Curve 4 or that it be placed with a minimum of 6 passes of the roller. Recommended placement densities and moisture contents are shown on Form SCS-372.

Embankment Design

A standard embankment design of 2-1/2:1 slopes should be stable.

Residual settlement within the embankment should not exceed 2-1/2% of the height of fill.

Considering foundation consolidation during construction, a total allowance of 1.2' should be added to the fill height for settlement of the foundation and embankment.

Drainage

No drainage measures are recommended.



CC: M. P. Frank, Fort Worth, Texas
Gene Vittetoe, Fort Worth, Texas
P. M. Browning, Temple, Texas
D. L. Bidwell, Seguin, Texas
H. H. Swope, Waco, Texas
Rey S. Decker, Lincoln, Nebraska

COMPACTION AND PENETRATION RESISTANCE REPORT

 Date 12-28-61 Sample No.: Field Comp. #1 Lab R62-1196

 Project Plum Creek Site 12 Location Texas

 Sample Location and Depth Borrow 1' - 5'



 Signature: LPM


| TYPE OF TEST | | TEST PROCEDURE | | Classification | |
|-------------------------------------|------------------|------------------|--------------|----------------|------------------|
| <input type="checkbox"/> | Standard Proctor | Weight of Hammer | 10 lbs. | 100 | % Water |
| <input checked="" type="checkbox"/> | Modified AASHTO | Drop | 18 inches | # 4 | Sieve |
| <input type="checkbox"/> | Other | Lifts | 5 | 2.70 | Specific Gravity |
| | | Vol. of Cylinder | 1/30 Cu. Ft. | 1 | of 4 |

COMPACTION AND PENETRATION RESISTANCE REPORT

Date 12-28-61 Sample No.: Field Comp. #2 Lab F62-1197
Project Plan Creek Site 12 Location Texas
Sample Location and Depth Borrow 3' - 8'


Signature [Signature]



Unit wt. of rock = 159 pcf
Moisture in rock = 2%

| TYPE OF TEST | | TEST PROCEDURE | | Classification | |
|-------------------------------------|------------------|------------------|--------------|--------------------------------|----------------------|
| <input checked="" type="checkbox"/> | Standard Proctor | Height of Hammer | 5.5 lbs. | 100 | % Material Compacted |
| <input type="checkbox"/> | Modified AASHO | Drop | 12 inches | Passed #4 | Sieve |
| <input type="checkbox"/> | Other | Lifts | 3 | (3% Gr.) G _u - 2.67 | gr/cc |
| | | Vol. of Cylinder | 1/30 cu. ft. | Carve | 2 of 4 |

COMPACTION AND PENETRATION RESISTANCE REPORT


Date 12-28-61 Sample No.: Field Comp. #4 Lab P62-1199Project Plum Creek Site 12 Location TexasSample Location and Depth 4 Spillway 0' - 6'Signature: LPM

| TYPE OF TEST | TEST PROCEDURE | Classification |
|------------------|---------------------------|---------------------------------|
| Standard Proctor | Relay #1 Hammer <u>10</u> | <u>CH</u> |
| Modified Proctor | Drop <u>18</u> | <u>100</u> % Material Compacted |
| Other | Layer <u>5</u> | Factor <u>#4</u> |
| | Moisture <u>1/30</u> | Factor <u>2.66</u> |
| | Moisture <u>1/30</u> | Factor <u>3</u> |

COMPACTION AND PENETRATION RESISTANCE REPORT


Date 12-28-61 Sample No.: Field Comp. #5 Lab R62-1200
Project Plum Creek Site 12 Location Texas
Sample Location and Depth 6 Spillway 1' - 9'

Signature [Signature]



1045 119.2
1852 12.64 36

40%
36%
30%
20%
10%
0%



Unit wt of rock = 159 pcf

Moisture in rock = 2%


8 10 12 14 16 18 20 22 24 26 28

| | | | |
|------------------|------|------|----|
| Moisture Content | 25 | 100 | GC |
| Plasticity Index | 12 | 4 | |
| Shrinkage | 3 | 2.66 | |
| Roll of Curves | 1/30 | 4 | 4 |

RECOMMENDED USE OF EXCAVATED MATERIAL

☐ Formal Zoning Plan ☒ Selective Placement Plan

State Texas
Project Flom Co. Site 12
Date 1-2-62
By JH



TYPICAL EMBAYMENT SECTION

[illegible]